

2024-00000480



Auburn Indiana Septage Tank

Job Location: Auburn Indiana

Auburn Indiana WPC

2010 S Wayne St
Auburn, IN 46706

Advanced Rehabilitation Technology

525 Winzeler Drive
Bryan, Ohio 43506
United States

Daniel E. Rabe

Operations / Industrial Pretreatment
derabe@ci.auburn.in.us
260-925-1714

Prepared by:

Derrick Short

"Indiana / Illinois Field Manager "

derrick@artcoatingtech.com
+14195510506

Quote created: March 7, 2024
Quote valid till: April 6, 2024

PRODUCTS & SERVICES	UNIT QUANTITY	UNIT PRICE	TOTAL
Lining of Septage Tank	1	\$30,782.50	\$30,782.50
Total			\$30,782.50

Signature

Date

Printed name



Jennifer Hoop
PO BOX 36726
Indianapolis, IN 46236
Office Phone 317-428-6543
www.concospray.com
Email: jhoop@concospray.com



Date: 3/6/2024
To: Dan Rabe
Owner: Auburn Water Pollution Control
Re: Rehabilitation of Septage Receiving Tank

Item No.	Item	Unit	Est Qty	Unit Price	Amount
1	Mobilization	LS	1.00	\$ 2,500.00	\$ 2,500.00
2	Vapor Blasting of Steel Tank using glass media	LS	1.00	\$ 9,400.00	\$ 9,400.00
3	Sprayroq Sprayshield Green II Lining	LS	1.00	\$ 20,900.00	\$ 20,900.00
Total					\$ 32,800.00

Scope: We will first vapor blast the existing steel to provide a commercial blast cleaning and profile. The blasting will take approximately 2 days. All media will need to be removed by vac truck and we will tape and protect all areas not to receive lining. The steel will then receive a primer over all areas receiving lining. The lining will begin when there is a 5 degree spread between ambient temperature and dew point to assure correct moisture for lining. The ambient temperature needs to be 60 degrees or more. The Sprayroq Sprayshield Green II polyurethane lining will be applied at a thickness of 125-150 mils. Structure can be returned to service within an hour of completion. Process to take 4-5 days.

By Owner: Initial Shutdown and Cleaning of Structure at least one day before we mobilize
Vac Truck Service after Vapor Blasting to remove all media
Water access needed
Overnight parking of Equipment

Terms: Quote is good for 30 days
No winter conditions is included in pricing
Payment terms of net 30 days of completion.



Conco Spray Solutions is a Certified WBE & INDOT DBE