

Electric Motors | Air Compressors | Custom Cranes & Hoists

Founded in 1953, Brehob emphasizes customer service above all else.

August 26, 2024

CITY OF AUBURN WATER POLLUTION CONTROL 2010 WAYNE ST AUBURN, IN 46706 ATTN: DANIEL RABE Quote # 308-24-097BP Phone # 260-235-0742

Email: DERABE@CLAUBURN.IN.US

DANIEL,

The following is your price for: BREHOB TO PROVIDE AND INSTALL (1) 4500# MONORAIL SYSTEM AND MANUAL HOIST. INSTALL IS QUOTED FOR STANDARD TIME M-F. BREHOB TO PROVIDE INSTALL EQUIPMENT. FIRST INSPECTION INCLUDED.

MONORAIL CRANE SYSTEM

Monorail Capacity: 4500 (2.25 Ton)

Overall Monorail Length: 21'-0" Support Distance: 19'-0"

Height Under Boom: 15'-0"

Overall Height: 16'-8" +/
Beam Size: W10

Header Support Width: 18'-0"

CM HURRICANE HOIST

Base Weight (lb) 201 Hoist Platform HU

Operating Environment Normal

Hoist Suspension Type Army Type Hand-Geared Trolley

Rated Lift Capacity 3 Metric Ton Requested Lift Distance (ft) 15.0 Reeving Style I-Part Single Reeved Rope/Chain Finish Zinc Plated

Hoist Hand Chain Drop (ft) 13.0

Tioist Hand Chain Drop (11) 13.

Hand Chain Finish Zinc Plated

Lower Hook Material Steel

Lower Hook Type Latch Type

Load Limiter Option Load Limiter

Paint Finish Powder Coat

Paint Color Orange

Trolley Selection Model Hurricane (Integrated)

Trolley Type Geared Trolley

Trolley Drive Configuration 4 Wheel Rigid, Single Geared

Rated Trolley Capacity 3 metric tonnes

Trolley Hand Chain Drop (ft) 13.0


Hand Chain Finish Zinc Plated

Beam Flange Width (in) 5.000

Trolley Flange Width Adj. Range 3.940 - 7.090

Trolley Wheel Tread Style Compound

Trolley Wheel Tread Diameter 4.41 in (11.20 cm)





Electric Motors | Air Compressors | Custom Cranes & Hoists

Trolley Wheel Material Forged Steel Trolley Wheel Quantity 4 Trolley Drop Stops Included Trolley Drop-Stop Material Steel Trolley Paint Finish Powder Coat Trolley Paint Color Black

12-14 WEEKS LEAD TIME AFTER APPROVAL DRAWINGS 2-3 WEEKS FOR APPROVAL DRAWINGS

MATERIAL PRICE: \$11,700.00


INSTALL: \$6,726.00

EQUIPMENT: \$1,058.00 TOTAL INSTALL PRICE: \$19,484.00

Effective January	I,	2019 if	credit	cards	are i	ised t	hey w	ill h	ave a .	3 %	surcharge

•	Subject to tariff & surcharge increases
•	Sales tax is not included if applicable
•	Freight IS NOT included if applicable
•	Brehob to provideEQUIPMENT FOR INSTALL
•	Labor rate is based on MonFri, 7:30 am to 4:00 pm
•	Estimated 12 To 14 week delivery after signed approval drawing if applicable, receipt of PO # with signed copy of quote and customer credit approval
•	Due to any unforeseen potential issues related to COVID-19, delays may occur

- Customer to provide clear work area & access to equipment
- Delays: Any delays, caused by the customer, that result in additional charges to be incurred by Brehob shall be billed to the customer in addendum to the quoted amount.
- Quote good for 30 days





Electric Motors I Air Compressors | Custom Cranes & Hoists

• 25% DOWN PAYMENT 75% NET 30			
Customer responsibility to obtain load test	t. Load test will be quoted if ne	eeded	
• 10 year warranty			
• FOB – (Brehob or factory)			
• Net 30 days with approved credit			
• Please reference Brehob's quote number	on your PO & all correspond	<u>dence</u>	
Thank you for the opportunity to quote thi	is project. I look forward to heari	ing from you.	
Sincerely,			
Branden Pence			
This order is hereby acknowledged and accepted For ISO requirements please date, sign, affix PO			
By Customer:	Date:	PO#:	
		Reviewed By:	Date:



1500 WOHLERT STREET ANGOLA, IN 46703

*www.OneCraneSource.com

PHONE 260.665.2130 FAX 260.665.2315

Auburn WWTP 2010 Wayne St. Auburn, IN 46706 260-925-1714

July 23, 2024

Attn: Daniel Rabe

Subject: Crane and Runway Star Crane Quote #0020517SM

Item 1

Crane: Monorail Workstation

(1) Workstation Capacity Runway:

Style:

Overall Length: Overall Width:

Height Under Beam:

Columns: Paint

(1) Hoist/Trolley

Model Style: Lift: Trolley: * 2 ½ Ton. (5,000 lbs.)

* Free standing

* 21'-0" approximate * 18'-0" approximate

* 15'-0"

* 4 total with tie backs as needed

* Yellow (water base)

* CM Cyclone 2 1/2 Ton Chain Hoist

* Manual

* 15' available on hoist

* Manual

Price for above items delivered and installed:

\$ 35,423.00 + tax not included

Customer Notes:

- -If runway cannot be tied back to the building footings will be required.
- -Does not include equipment rental for setting system.
- -Making are clear and accessible for installation.

Terms:

- 1. Freight to jobsite is include in the above price.
- 2. Bonding and permits are not included in above price. Applicable bonding rates will be added to the above costs, and permits are the responsibility of the general contractor.
- 3. Stamped PE drawings are not included in above pricing.
- 4. Freight costs are based on shipping entire order in one shipment using standard LTL carriers. All partial shipments or express freight carriers, requested by the customer, are an extra cost to this quotation. Also, if fuel costs continue to increase, there is the potential for fuel surcharges that will reflect the change in fuel costs from quote date to ship date.
- 5. This quotation is firm for acceptance for (30) days, and is based on receiving a mutually acceptable contract within this time frame.
- 6. Hoist & crane materials in this quotation are based on current pricing. Prices are firm, provided shipment can be made within six months from the date of this quotation. Materials shipped after 6 months from the date of this quotation will be subject to potential escalation costs, which will be based directly on any increased material or freight costs that we incur.
- 7. This quotation is based on straight time rates, Monday through Friday. 8AM to 4:30PM, and

Your One Source For:

Abus, Acco-Wright, ARO, Budgit, CM, Coffing, Chester, Dayton, Demag, Detroit, Electro-Lift, Gardner-Denver, Gorbel, Harrington, Ingersol Rand, Jet, Kone, LodeRail, P&H, R&M, Shaw-Box, Shepard-Niles, Stahl, Yale and other related products (see line card)



1500 WOHLERT STREET ANGOLA, IN 46703

*www.OneCraneSource.com

PHONE 260.665.2130 FAX 260.665.2315

clear accessibility to work area.

8. Above prices are quoted to the best of our ability; however, if any additional material or labor is needed, it will be brought to your attention before the work is completed.

9. Standard payment terms are Net 15 Days from date of invoice, for customers with a pre-approved credit account.

10. Material subject to cancellation fees if ordered and cancelled by customer. No returns on non-standard, special or engineered ordered parts all sales are final.

Payment Terms: 40% down with PO, 40% due before delivery, balance net 15 days upon delivery/installation.

This Quote is based on current raw material market pricing. Due to the current volatility, we reserve the right to implement a steel and or ASCE rail surcharge to this order.

If you have questions, please call at your convenience.

Sincerely,

Scott May